BRUHAT BANGALORE MAHANAGARA PALIKE

DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division

DRAFT TENDER SHEDULE COPY

Name of Work: Maintenance of Crematorium, Burrial Grounds & Office Maintenance in Ward No 14 Bagalagute, Dasarahalli Sub Division

Sl	Description of Work	Unit	Qty	Rate to be Quoted	
				In figures (Rs)	In Words (Rs)
1	2	3	4	5	6
1	Clearing and grubbing road land including uprooting rank vegetation, grass, brush, shrubs, saplings and trees of girth upto 300mm, by manual means, in area of light jungle, removal of stumps, disposal of unserviceable materials, stacking of serviceable materials labour charges complete as per specifications.	~~Cum~~ Sqm	16650.00		
2	Excavation for roadway in hard rock (blasting prohibited) with rock breakers including breaking rock, loading in tippers and disposal and trimming bottom and side slopes in accordance with requirements of lines, grades and cross sections complete as per specifications..	Cum	337.50		

Signature of the Contractor

Executive Engineer
Dasarahalli Division

ಮುಖ್ಯ ಆಡಳಿತಾಧಿಕಾರಿ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು